

Geoton Pty Ltd ABN 81 129 764 629 PO Box 522 Prospect TAS 7250 Unit 24, 16-18 Goodman Court Invermay TAS 7248 Tel (+61) (3) 6326 5001 www.geoton.com.au

29 January 2024

Reference No. GL21145Bc

Mr Nick Campion 162 Wingaroo Road MEMANA TAS 7255

Dear Sir

RE: On-site Wastewater Disposal Assessment and Design 162 Wingaroo Road, Memana

We have pleasure in submitting herein our report detailing the results of the geotechnical investigation conducted at the above site.

Should you require clarification of any aspect of this report, please contact Brett Street on (03) 6326 5001.

For and on behalf of

Geoton Pty Ltd

Tony Barriera Director – Principal Geotechnical Engineer

1 INTRODUCTION

A limited scope investigation has been conducted for Mr Nick Campion at the site of a proposed residential unit development at 162 Wingaroo Road, Memana.

The investigation has been conducted to assess the suitability of the site for the disposal of domestic wastewater and the design of an on-site wastewater system in accordance with AS/NZS 1547:2012 "On-site Domestic Wastewater Management".

No plans of the proposed development were provided; however, we understand a 2bedroom unit is proposed to be constructed approximately 40m north of the existing dwelling.

2 FIELD INVESTIGATION

The field investigation was conducted on 31 March 2021 and involved the drilling of 3 boreholes by hand auger to depths 0.8m to 1.1m.

The permeability of the site was tested using a Constant Head Permeameter.

The logs of the boreholes are included in Appendix A and their locations are shown on Figure 3 attached.

3 SITE CONDITIONS

The site is a large farming acreage and is currently developed with an existing dwelling. The proposed unit is to be located on generally level ground approximately 40m north of the existing dwelling. The proposed wastewater disposal area is to be located to the northeast of the unit.

The Mineral Resources Tasmania (MRT) Digital Geological Atlas, 1:250,000 Series, shows the site to be located on Quaternary period sediments.

Examination of the LIST Landslide Planning Map – Hazard Bands Overlay indicates that the site is not within a mapped landslide hazard band.

The investigation indicated that the soil profile was generally uniform over the site. The boreholes generally encountered a silty sand topsoil to depths of 0.1m to 0.15m, overlying sand to depths of 0.35m to 0.65m, underlain by sandy clay to the investigated depths of 0.9m to 1.1m.

The boreholes did not encounter any signs of groundwater seepage over the investigated depths.

4 EFFLUENT DISPOSAL

The AS/NZS 1547:2012 and the *Building Act 2016:* Director's Guidelines for On-site Wastewater Management Systems provide guidelines for typical wastewater flow allowances under a range of circumstances. The documents recommend a typical wastewater flow of 120 litres/person/day for households on a tank water supply. As the unit is 2-bedrooms with a population equivalent of 4, a value of 480L/day has been adopted.

4.1 Permeability of Soil and Soil Category

The soil has been classified as follows:

- Texture Sandy Loam (Table E1 from AS1547-2012);
- Structure Massive (Table E4 from AS/NZS1547-2012); and
- Category 2 (Table E1 from AS/NZS1547:2012).

The permeability (K_{sat}) at the site was measured at 1.4m/day. For massive structured Category 2 soils the indicative permeability from AS/NZS1547 Table 5.1 is 1.4 - 3.0m/day. Therefore, the permeability is within the range for massively structured Category 2 soils.

• Adopted Permeability – 1.4m/day.

4.2 Disposal and Treatment Method

This site assessment indicates that the site is suitable for the disposal of domestic effluent by way of a septic tank, which is required to have a minimum capacity of **3,000L**, and absorption trenches.

Due to the limited sandy soil horizon, it is a requirement to increase the encountered sandy soil profile by a minimum of 400mm. The sandy material can be site-sourced. This will allow a minimum 600mm separation from the base of the trench to the encountered silty clay.

4.3 Design Loading Rate

The adopted design loading rate for the absorption trenches has been set at the conservative rate of 15mm/day as outlined in AS/NZS 1547:2012 Table L1.

4.4 Absorption Trench System

Guidelines for the design of the trench systems are outlined in AS/NZS 1547:2012 Appendix L. The method of determining the dimensions for the trenches is outlined in AS/NZS 1547:2012 Section L4 and is as follows:

$$L = \frac{Q}{DLR \times W}$$

Where L = Length in metres

Q = Design daily flow in L/day

DLR = Design Loading Rate in mm/day

W = Trench width in metres (set at 1.0m)

As the DLR value has been set at 15mm/day and the design daily flow (Q) has been set at 480L/day, when the parameters are inserted in the above equation the trench dimensions required are as follows:

- Trench length = 32 (2 x 16m trenches)
- Trench width = 1.0m
- Trench depth = 0.5m
- A downslope separation of 2m (minimum) must be left between trenches.

This would give a disposal area of approximately 64m².

There is adequate secondary (back-up) area of 64m² if required.

The trenches are to be located within the area shown on the site plan. A distribution box is to be installed to ensure even distribution of effluent to the two trenches.

The trench is to be constructed as per the cross-section shown on Figure WW-02 attached.

4.5 Pump-Out Chamber

Due to the gentle fall of the site, a pump and pump pit may be required once levels have been confirmed after site works.

The pump is to be hard-wired to the dwelling and comes fitted with audible and visual high-water alarms. The alarms will notify you of a failing submersible pump or blocked line, which causes the liquid level to rise in your septic tank/pump pit.

4.6 Setbacks

The minimum separation distance between the disposal area and horizontal and vertical features is based on Appendix R from AS/NZS 1547:2012 "Recommended Setback Distances for Land Application Systems" and Section 3.1 from the *Building Act 2016:* Director's Guidelines for On-site Wastewater Management Systems. The following setbacks are required:

- 22.0m from downslope watercourses and sensitive features;
- 2.0m from downslope property boundaries;
- 1.5m from cross-slope or up-slope property boundaries;
- 4.0m from buildings situated cross-slope or up-slope; and
- 5.0m from downslope buildings.

4.7 Wastewater Recommendations

It is recommended that the following actions are undertaken in looking after your system:

 Septic tanks <u>must be</u> pumped out at least every 3 to 5 years or more frequently depending on usage;

- Minimise domestic water use;
- Minimise the use of non-biodegradable detergents;
- Minimise the use of detergents containing phosphorous (eg calgon and similar);
- Avoid discharging polluting chemicals into wastewater systems; and
- Monitor quality of groundwater.

References:

AS 1726 - 2017 Geotechnical Site Investigations AS/NZS 1547- 2012 On-site Domestic Wastewater Management *Building Act 2016:* Director's Guidelines for On-site Wastewater Management Systems

Attachments:

Limitations of report Figure 1 – Locality Plan Figure 2 – Site Plan Figure 3 – Wastewater Disposal Plan Figure WW-02 – Typical Trench Section Appendix A – Borehole Logs & Explanation Sheets Appendix B – Certificate Forms

GEOTON Pty Ltd Geotechnical Consultants - Limitations of report

These notes have been prepared to assist in the interpretation and understanding of the limitations of this report.

Project specific criteria

The report has been developed on the basis of unique project specific requirements as understood by Geoton and applies only to the site investigated. Project criteria are typically identified in the Client brief and the associated proposal prepared by Geoton and may include risk factors arising from limitations on scope imposed by the Client. The report should not be used without further consultation if significant changes to the project occur. No responsibility for problems that might occur due to changed factors will be accepted without consultation.

Subsurface variations with time

Because a report is based on conditions which existed at the time of subsurface exploration, decisions should not be based on a report whose adequacy may have been affected by time. For example, water levels can vary with time, fill may be placed on a site and pollutants may migrate with time. In the event of significant delays in the commencement of a project, further advice should be sought.

Interpretation of factual data

Site assessment identifies actual subsurface conditions only at those points where samples are taken and at the time they are taken. All available data is interpreted by professionals to provide an opinion about overall site conditions, their likely impact on the proposed development and recommended actions. Actual conditions may differ from those inferred to exist, as it is virtually impossible to provide a definitive subsurface profile which includes all the possible variabilities inherent in soil and rock masses.

Report Recommendations

The report is based on the assumption that the site conditions as revealed through selective point sampling are indicative of actual conditions throughout an area. This assumption cannot be substantiated until earthworks and/or foundation construction is almost complete and therefore the report recommendations can only be regarded as preliminary. Where variations in conditions are encountered, further advice should be sought.

Specific purposes

This report should not be applied to any project other than that originally specified at the time the report was issued.

Interpretation by others


Geoton will not be responsible for interpretations of site data or the report findings by others involved in the design and construction process. Where any confusion exists, clarification should be sought from Geoton.

Report integrity

The report as a whole presents the findings of the site assessment and the report should not be copied in part or altered in any way.


Geoenvironmental issues

This report does not cover issues of site contamination unless specifically required to do so by the client. In the absence of such a request, Geoton take no responsibility for such issues.




	Approxima	te Scale (m)	
0	500	1000	1500


C				client: MR NICK CAMPION					
G	EOI		Pty Ltd	project:	162 WINGAROO	ROAD			
date	29/01/2024	drawn	BS		MEMANA				
scale	AS SHOWN	approved	ТВ	title:	LOCALITY PL	AN			
original size	A3	rev		project no:	GL21145B	figure no.	1		



					client: MR NICK CAMPION					
	G			Pty Ltd	project: 162 WINGAROO ROAD					
(date	29/01/2024	drawn	BS		MEMANA				
	scale	AS SHOWN	approved	ТВ	title:	SITE PLAN				
	original size	A3	rev		project no:	GL21145B	figure no. 2			




Approximate Scale (m)



Due to the limited sandy soil horizon, it is a requirement to increase the encountered sandy soil profile by a minimum of 400mm, the sandy material can be site-sourced. This will allow a minimum 600mm separation from the base of the trench to the encountered silty clay.

	Legend					client:	MR NICK CAM	PION	
BH 1					Pty Ltd	project: 162 WINGAROO ROAD			
•	Approximate Borehole Location				MEMANA				
		scale	AS SHOWN	approved	ТВ	title:	WASTEWATER DISP	OSAL PLAN	
		original size	A3	rev		project no:	GL21145B	figure no.	3



Appendix A

Borehole Logs

ENGINEERING BOREHOLE LOG

Geotechnical Consultants

PO Box 522 Prospect TAS 7250 Unit 24, 16-18 Goodman Court, Invermay TAS Tel (03) 6326 5001 Borehole no. BH1 Sheet no. 1 of 1 Job no. GL21145A

С	lier	nt :			Mr Nick (Campior	1					Date :	31/03/21
	roje							ispos	al Assessment & Design			Logged By :	BS
Lo	oca	itic	on :		162 Wing	162 Wingaroo Road, Memana							
			ode		Hand Au	ger			Easting: Slope: 90 ⁰			RL Surface :	
H	ole	di	iam	eter	: 55mm			N	orthing: Bearing: -		-	Datum :	
Method	Support	- 00000	Penetration	Water	Notes Samples Tests (DCP)	Depth (m)	Graphic log	Classification Symbol		Moisture condition	Consistency density index		additional /ations
						-		SM	TOPSOIL - Silty Sand, fine/medium grained, black/brown	М	MD/ L		-
						0.25		SW	SAND - medium/coarse grained, light brown/grey	М	MD		
H	z	:				0.50		CH	Silty CLAY - high plasticity, orange	М	St		
						1.00 1.25 1.25 1.50 1.75 2.00 2.25			Borehole BH1 terminated @ 0.9m				

ENGINEERING BOREHOLE LOG

Geotechnical Consultants

PO Box 522 Prospect TAS 7250 Unit 24, 16-18 Goodman Court, Invermay TAS

Tel (03) 6326 5001

Borehole no. BH2 Sheet no. 1 of 1 Job no. GL21145A

С	lien	t :		Mr Nick C	Campior	۱					Date : 31/03/21	
Pi	roje	ct :		Onsite W	astewat	er D	ispos	al Assessment & Design			Logged By : BS	
		tion :			162 Wingaroo Road, Memana							
		node 		Hand Au	ger			Easting: Slope: 90 ⁰			RL Surface :	
н	ole	diam	eter	: 55mm	1	I	N	orthing: Bearing: -		Ś	Datum :	- 1
Method	Support	Penetration	Water	Notes Samples Tests (DCP)	Depth (m)	Graphic log	Classification Symbol		Moisture condition	Consistency density index		
					-		SM	TOPSOIL - Silty Sand, fine/medium grained, black/brown	М	MD/		-
HA	z				0.25		SW	SAND - medium/coarse grained, light brown/grey	М	MD		
					0.75 - - 1.00		СН	Silty CLAY - high plasticity, orange	М	St		
					1.25 1.50 1.75 2.00 2.25			Borehole BH2 terminated @ 1.1m				

ENGINEERING BOREHOLE LOG

Geotechnical Consultants

PO Box 522 Prospect TAS 7250 Unit 24, 16-18 Goodman Court, Invermay TAS Tel (03) 6326 5001 Borehole no. BH3 Sheet no. 1 of 1 Job no. GL21145A

Cli	ien	t :			Mr Nick C	Campion)					Date :	31/03/21
	oje							•	al Assessment & Design			Logged By :	BS
	cat				162 Wing		oad,						
			del		Hand Aug	ger			Easting: Slope: 90 ⁰			RL Surface :	
но	bie	ais	ame	eter :	55mm			IN	orthing: Bearing: -	_	, Ś	Datum :	
Method	Support	:	Penetration	Water	Notes Samples Tests (DCP)	Depth (m)	Graphic log	Classification Symbol		Moisture condition	Consistency density index		
						-		SM	TOPSOIL - Silty Sand, fine/medium grained, black/brown	М	MD/ L		-
						0.25		SW	SAND - medium/coarse grained, light brown/grey	М	MD		-
ΗA	z					- 0.50 - -		СН	Silty CLAY - high plasticity, orange	М	St		-
						0.75			Borehole BH3 terminated @ 0.8m				-
						_ _ 							-
						- - 1.25							
						- - - 1.50							-
						-							-
						<u>1.75</u>							
						2.00							
						2.25							-

Investigation Log Explanation Sheet

METHOD - BOREHOLE

TERM	Description
AS	Auger Screwing*
AD	Auger Drilling*
RR	Roller / Tricone
W	Washbore
СТ	Cable Tool
HA	Hand Auger
DT	Diatube
В	Blank Bit
V	V Bit
Т	TC Bit

* Bit shown by suffix e.g. ADT

METHOD – EXCAVATION

TERM	Description
N	Natural exposure
х	Existing excavation
н	Backhoe bucket
В	Bulldozer blade
R	Ripper
E	Excavator

SUPPORT

TERM	Description
М	Mud
N	Nil
С	Casing
S	Shoring

PENETRATION

1	2	3	4	
				No resistance ranging to Refusal

WATER

Symbol	Description
	Water inflow
	Water outflow
	17/3/08 water on date shown

NOTES, SAMPLES, TESTS

,			
TERM	Description		
U ₅₀	Undisturbed sample 50 mm diameter		
U ₆₃	Undisturbed sample 63 mm diameter		
D	Disturbed sample		
Ν	Standard Penetration Test (SPT)		
N*	SPT – sample recovered		
Nc	SPT with solid cone		
V	Vane Shear		
PP	Pocket Penetrometer		
Р	Pressumeter		
Bs	Bulk sample		
Е	Environmental Sample		
R	Refusal		
DCP	Dynamic Cone Penetrometer (blows/100mm)		
PL	Plastic Limit		
LL	Liquid Limit		
LS	Linear Shrinkage		

CLASSIFICATION SYMBOLS AND SOIL DESCRIPTION

Based on AS 1726:2017

MOISTURE

TERM	Description		
D	Dry		
Μ	Moist		
W	Wet		

CONSISTENCY/DENSITY INDEX

TERM	Description
VS	very soft
S	soft
F	firm
St	stiff
VSt	very stiff
н	hard
Fr	friable
VL	very loose
L	loose
MD	medium dense
D	dense
VD	Very dense

Soil Description Explanation Sheet (1of 2)

DEFINITION

In engineering terms, soil includes every type of uncemented or partially cemented inorganic or organic material found in the ground. In practice, if the material can be remoulded or disintegrated by hand in its field condition or in water it is described as a soil. Other materials are described using rock description terms.

CLASSIFICATION SYMBOL AND SOIL NAME

Soils are described in accordance with the AS 1726: 2017 as shown in the table on Sheet 2.

PARTICLE SIZE DEFINITIONS

NAME	SUBDIVISION	SIZE (mm)		
BOULDERS		>200		
COBBLES		63 to 200		
	Coarse	19 to 63		
GRAVEL	Medium	6.7 to 19		
	Fine	2.36 to 6.7		
	Coarse	0.6 to 2.36		
SAND	Medium	0.21 to 0.6		
	Fine	0.075 to 0.21		
SILT		0.002 to 0.075		
CLAY		<0.002		

MOISTURE CONDITION

Coarse Grained Soils

Dry	Non-cohesive and free running.
Moist	Soil feels cool, darkened in colour.
	Soil tends to stick together.
Wet	As for moist but with free water forming when
	handling.
Fine Grai	ned Soils
	ned Soils y of Plastic Limited – w < PL
Moist, dr	y of Plastic Limited – w < PL
Moist, dr	y of Plastic Limited – w < PL Hard and friable or powdery.

approximately equal to the plastic limit. Moist, wet of Plastic Limit – w > PL Soils usually weakened and free water forms on hands when handling. Wet, near Liquid Limit - w ≈ LL Wet, wet of Liquid Limit - w > LL

CONSISTENCY TERMS FOR COHESIVE SOILS

TERM	UNDRAINED STRENGTH su (kPa)	FIELD GUIDE
Very Soft	≤12	Exudes between the fingers when squeezed in hand
Soft	12 to 25	Can be moulded by light finger pressure
Firm	25 to 50	Can be moulded by strong finger pressure
Stiff	50 to 100	Cannot be moulded by fingers
Very Stiff	100 to 200	Can be indented by thumb nail
Hard	>200	Can be indented with difficulty by thumb nail
Friable	_	Can be easily crumbled or broken into small pieces by hand

RELATIVE DENSITY OF NON-COHESIVE SOILS

TERM	DENSITY INDEX (%)		
Very Loose	≤15		
Loose	15 to 35		
Medium Dense	35 to 65		
Dense	65 to 85		
Very Dense	> 85		

DESCRIPTIVE TERMS FOR ACCESSORY SOIL COMPONENTS

DESIGNATION OF COMPONENT	GR	OARSE AINED OILS	IN FINE GRAINED SOILS		
DESIGNATION OF COMPONENT	% Fines	% Accessory coarse fraction	% Sand/ gravel	TERM	
Minor	≤5	≤15	≤15	Trace	
Minor	>5, ≤12	>15, ≤30	>15, ≤30	With	
Secondary	>12	>30	>30	Prefix	

SOIL STRUCTURE

ZONING	Ì	CEMENTING		
Layer	Layer Continuous across the exposure or sample.		Easily disaggregated by hand in air or water.	
Lens	Discontinuous layer of different material, with lenticular shape.	Moderately cemented	Effort is required to	
Pocket	An irregular inclusion of different material.		disaggregate the soil by hand in air or water.	

GEOLOGICAL ORIGIN

WEATHERED IN PLACE SOILS

Extremely Weathered material	Material is weathered to such an extent that it has soil properties. Structure and/or fabric of parent rock material retained and visible.
Residual soil	Structure and/or fabric of parent rock material not retained and visible.

TRANSPORTED SOILS

Aeolian soil	Carried and deposited by wind.
Alluvial soil	Deposited by streams and rivers.
Colluvial soil	Soil and rock debris transported downslope by gravity.
Estuarine soil	Deposited in coastal estuaries, and including sediments carried by inflowing rivers and streams, and tidal currents.
Fill	Man-made deposit. Fill may be significantly more variable between tested locations than naturally occurring soils.
Lacustrine soil	Deposited in freshwater lakes.
Marine soil	Deposited in a marine environment.

Soil Description Explanation Sheet (2 of 2)

SOIL CLASSIFICATION INCLUDING IDENTIFICATION AND DESCRIPTION

		TION PROCEDUR			LODING IDENTITICA		GROUP	
(Excluding particles larger than 63 mm and basing fractions on estimated mass)					SYMBOL	PRIMARY NAME		
size	lf of on is mm	CLEAN GRAVEL (Little or no fines)		Wide range in grain size and substantial amounts of all intermediate particle sizes		GW	GRAVEL	
		CLEAN GRAVEL (Little or no fines)		Predominantly one size or a range of sizes with some intermediate sizes missing		GP	GRAVEL	
SOIL ding ove 075 mm	eyes)	GRAVEL More than ha coarse fractic ger than 2.3	GRAVEL WITH FINES (Appreciable amount of fines)		n-plastic fines (for identi e ML and MH below)	fication procedures	GM	Silty GRAVEL
AINED oil excluc	o naked	la la	GRA WITH (Appre amo of fii		astic fines (for identificati ., CI and CH below)	on procedures see	GC	Clayey GRAVEL
SFAINED SOIL COARSE GRAINED SOIL of soil excluding oversize More than 65% of soil excluding oversize naller than 0.075 mm fraction is larger than 0.075 mm AY SILT & CLAY T AY SILT & CLAY T AY SILT & CLAY T Ay Sabout the smallest particle visible to naked eyes) GRAVEL AY SaND Coarse fraction is Ay T More than half of More than half of Ay T SaND Coarse fraction is Ay T SaND T Ay T T SaND Ay T SaND T Ay T T SaND Ay T T SaND Ay T T SaND	t sur	CLEAN SAND (Little or no fines)	Wide range in grain size and substantial amounts of all intermediate sizes		SW	SAND		
	ND n half of action is n 2.36 m	CLE SA (Littl) no fi		Predominantly one size or a range of sizes with some intermediate sizes missing		SP	SAND	
	SA More tha coarse fi	SAND WITH FINES (Appreciable amount of fines)		Non-plastic fines (for identification procedures see ML and MH below)		SM	Silty SAND	
	u us	SA WITH (Appre amo of fii		Plastic fines (for identification procedures see CL, CI and CH below)		SC	Clayey SAND	
as	abo	IDENTIFICATIO	N PROCEDURES O	N FI	RACTIONS <0.075 mm			
versi nm	cle is		DRY STRENGTH		DILATANCY	TOUGHNESS		
IL ng o' 775 r	parti) iv, "	None to Low		Slow to Rapid	Low	ML	SILT
O SO cludi an 0.(шШ	SILT & CLAY (low to medium plasticity, LL ≤ 50)	Medium to High		None to Slow	Medium	CL, CI	CLAY
INED oil ex er tha	.075	L Dia C	Low to Medium		Slow	Low	OL	ORGANIC SILT
GRA of sc malle	(A 0	(A 0. A √	Low to Medium		None to Slow	Low to Medium	MH	SILT
FINE GRAINED SOIL More than 35% of soil excluding oversize fraction is smaller than 0.075 mm (A 0.075 mm particle is at	SILT & CLAY (high plasticity, LL > 50)	High to Very High		None	High	СН	CLAY	
	SILT pla	Medium to High		None to Very Slow	Low to Medium	ОН	ORGANIC CLAY	
More 1 fra		Highly Organic Soil	Readily identified by colour, odour, spongy feel and frequently by fibrous texture.			Pt	PEAT	
• LL – Liquid	Limit.	1					I	1

COMMON DEFECTS IN SOILS

TERM	DEFINITION	DIAGRAM	TERM	DEFINITION	DIAGRAM
PARTING	A surface or crack across which the soil has little or no tensile strength. Parallel or sub parallel to layering (e.g. bedding). May be open or closed.		SOFTENED ZONE	A zone in clayey soil, usually adjacent to a defect in which the soil has a higher moisture content than elsewhere.	ALCONTRACT OF ALCONTRACT
FISSURE	A surface or crack across which the soil has little or no tensile strength, but which is not parallel or sub parallel to layering. May be open or closed. May include desiccation cracks.		TUBE	Tubular cavity. May occur singly or as one of a large number of separate or inter-connected tubes. Walls often coated with clay or strengthened by denser packing of grains. May contain organic matter.	
SHEARED SEAM	Zone in clayey soil with roughly parallel near planar, curved or undulating boundaries containing closely spaced, smooth or slickensided, curved intersecting fissures which divide the mass into lenticular or wedge-shaped blocks.		TUBE CAST	An infilled tube. The infill may be uncemented or weakly cemented soil or have rock properties.	
SHEARED SURFACE	A near planar curved or undulating, smooth, polished or slickensided surface in clayey soil. The polished or slickensided surface indicates that movement (in many cases very little) has occurred along the defect.		INFILLED SEAM	Sheet or wall like body of soil substance or mass with roughly planar to irregular near parallel boundaries which cuts through a soil mass. Formed by infilling of open defects.	

Appendix B

Certificate Forms

CERTIFICATE OF THE RESPONSIBLE DESIGNER

Section 94 Section 106 Section 129 Section 155

То:	Mr Nick Campion		Owner name	05			
	162 Wingaroo Road		Address	Form 35			
	Memana Tas		7255	Suburb/postco			
			1200				
Designer detail	S:						
Name:	Tony Barriera			Category:	Civil Engineer Hydraulic - Domestic		
Business name:	Geoton Pty Ltd			Phone No:	03 6326 5001		
Business address:	P O Box 522						
	Prospect TAS		7250	Fax No:			
Licence No:	IEAust 471929, CC6220 P Email add	ress: tba	rriera@	geoton.com	au		
Details of the p	roposed work:						
				Designer's pro	iect		
Owner/Applicant	Mr Nick Campion			reference No.	GL21145Bc		
Address:	162 Wingaroo Road			Lot N	lo: 241027/77		
	Memana Tas		7255				
Type of work:	Building work	< 🗌		Plumbing worl	k X (X all applicable)		
Description of wor	k:						
New building on-site wastewater management system water / sewerage / stormwater / on-site wastewater management system /				addition / repair / removal / re-erection water / sewerage / stormwater / on-site wastewater			
Description of the	Design Work (Scope, limitation	ons or exe	clusions): (X all applicab	le certificates)		
Certificate Type:	Certificate		Re	sponsible Pra	actitioner		
	Building design		Ar	chitect or Build	ling Designer		
	□ Structural design		Er	igineer or Civil	Designer		
	☐ Fire Safety design	· · · ·		e Engineer			
	Civil design	v		vil Engineer or Civil Designer			
	K Hydraulic design			uilding Services Designer			
	Fire service design			ilding Services			
	Electrical design			ilding Services	ů.		
	Mechanical design			ilding Service	r; Architect, Building		
Plumbing design				signer or Engi			
	^D Other (specify)						
Deemed-to-Satisfy:	x	Performar	nce Solu [.]	tion: 🔲 (X	the appropriate box)		
Other details:	iments provided in Repo	rt GL21	145Bc,	-			

Design documents provided:

The following documents are provided with this Certificate -

Document description:		
Drawing numbers:	Prepared by:	Date:
Schedules:	Prepared by:	Date:
Specifications:	Prepared by:	Date:
Computations:	Prepared by:	Date:
Performance solution proposals:	Prepared by:	Date:
Test reports:	Prepared by:	Date:

Standards, codes or guidelines relied on in design process:	
All design documents are contained within report	
AS/NZS1547:2012 On-site domestic-wastewater management	

Any other relevant documentation:	
Attuileutien ee deeluneu	

Attribution as designer:

I Tony Barriera of Geoton Pty Ltd am responsible for the design of that part of the work as described in this certificate;

The documentation relating to the design includes sufficient information for the assessment of the work in accordance with the *Building Act 2016* and sufficient detail for the builder or plumber to carry out the work in accordance with the documents and the Act;

This certificate confirms compliance and is evidence of suitability of this design with the requirements of the National Construction Code.

	Name: (print)	Signed	Date
Designer:	Tony Barriera	barn	29/01/2024
Licence No:	CC6220P		

Assessment of Certifiable Works: (TasWater)
Note: single residential dwellings and outbuildings on a lot with an existing sewer connection are not considered to increase demand and are not certifiable.
If you cannot check ALL of these boxes, LEAVE THIS SECTION BLANK.
TasWater must then be contacted to determine if the proposed works are Certifiable Works.
I confirm that the proposed works are not Certifiable Works, in accordance with the Guidelines for TasWater CCW Assessments, by virtue that all of the following are satisfied:
The works will not increase the demand for water supplied by TasWater
The works will not increase or decrease the amount of sewage or toxins that is to be removed by, or discharged into, TasWater's sewerage infrastructure
The works will not require a new connection, or a modification to an existing connection, to be made to TasWater's infrastructure
The works will not damage or interfere with TasWater's works
The works will not adversely affect TasWater's operations
The work are not within 2m of TasWater's infrastructure and are outside any TasWater easement
I have checked the LISTMap to confirm the location of TasWater infrastructure
If the property is connected to TasWater's water system, a water meter is in place, or has been applied for to TasWater.

Certification:

I Tony Barriera of Geoton Pty Ltd being responsible for the proposed work, am satisfied that the works described above are not Certifiable Works, as defined within the *Water and Sewerage Industry Act 2008,* that I have answered the above questions with all due diligence and have read and understood the Guidelines for TasWater CCW Assessments.

Note: the Guidelines for TasWater Certification of Certifiable Works Assessments are available at: <u>www.taswater.com.au</u>

	Name: (print)	Signed	Date
Designer:	Tony Barriera	brown	29/01/2024



LOADING CERTIFICATE

To:	Mr Nick Campion		Owner /Agent	Certificate Ref:
	162 Wingaroo Road		Address	AS/NZS 1547:2012 Section 7.4.2
	Memana Tas	7255	Suburb/postcode	

Details of work: Id2 Wingaroo Road Lot No: 77 Address: 162 Wingaroo Road Certificate of title No: 241027/77 Memana Tas 7255 Certificate of title No: 241027/77 The work related to this certificate: On-site domestic-wastewater management (description of the work or part work being certified)

Certificate details:

In issuing this certificate the following matters are relevant -

Documents:	Report GL21145Bc dated 29/01/2024 Figure 1 – Locality Plan Figure 2 – Site Plan Figure 3- Wastewater Disposal Plan
	Figure WW-02 – Typical Trench Section
Relevant calculations:	Contained in the above
References:	AS/NZS1547:2012 On-site domestic-wastewater management
	AO/NZO1047.2012 On-site domestic-wastewater management

Substance of Certificate:

This certificate sets out the design criteria and the limitations associated with use of the system.

Wastewater Characteristics

Population equivalent used for this assessment= 4 (2 Bedroom)Wastewater volume (L/day) used for this assessment= 480 (120 Litres per person)Approximate blackwater volume (L/day)=192Approximate greywater volume (L/day)= 288

Soil Characteristics/Design Criteria

Texture (Table E1 from AS/NZS 1547)	= Sandy Loam
Soil category (Table E1 from AS/NZS 1547)	= 2
Soil structure (Table E4 from AS/NZS 1547)	= Massive structured
Indicative permeability (Table 5.1 from AS/NZS 1547	7) = 1.4-3.0m/day
Measured permeability	
Adopted permeability	= 1.4m/day
Adopted Design Loading Rate	= 15mm/day
Soil thickness for disposal	= >1.1m
Minimum depth (m) to water	= >1.1m

Dimensions for On-Site Treatment System

Disposal and treatment methods= Septic tank and effluent TrenchesSite modification and specific design = N/APrimary disposal area required= 64m²Reserve disposal area required= 64m²Location and use of Reserve area= Reserve area located to the north of theproposed existing dwelling. Currently vacant.Is there sufficient area available on-site for disposal (including reserve) = Yes

<u>Notes</u>

The purpose of the reserve area is to allow for future extension of the land application system to allow a factor of safety against unforseen malfunction or failure, perhaps following increased household occupancy or inadvertent misuse of the system.

The land application area may be reduced to account for flow reductions by water-saving devices, provided the organic loading rate is not higher than it would have been without the flow reduction.

Allowable Variation from Design Flow

Based on a septic tank capacity of 3,000L and wastewater design volume of 480L/day the allowable variation from design flow (peak loading events) would be an additional 520L/day (Total flow of 1000L/day as per table J1 of AS/NZS 1547:2012).

System Limitations

Consequences of overloading the system:

Overloading the system can result in failure of the septic tank and land application system. This is a serious health and environmental hazard and can lead to any one or more of the following:

- Spread of infectious disease;
- Breeding of mosquitoes and attraction of flies and rodents;
- Nuisance and unpleasantness;
- Pollution of waterways;

- Contamination of bores, wells and groundwater; and
- Alteration to local ecology.

Consequences of under loading the system:

Under loading the system may result in the bacteria to stop working and system failure.

Operation Requirements

Refer to Section T5.2.1 of AS/NZS 1547:2012 for additional requirements. For on-site system to work well the following is required:

- Reduce sludge building up through scraping all dishes to remove fats/grease; don't use a food waste disposal unit; and don't put sanitary napkins into the system.
- To keep bacteria working in the septic tank use biodegradable soaps; use a low phosphorous detergent; don't use powerful bleaches and disinfectants; and don't put chemicals or paint down the drain.
- Conservation of water will reduce the volume of effluent requiring disposal to the land application area, make it last longer and improve its performance.

Maintenance Requirements

Refer to Section T5.2.2 of AS/NZS 1547:2012 for additional requirements. Maintenance of the system should include the following:

- Septic tanks must be inspected at least annually and pumped out regularly once the scum and sludge occupy two thirds of the tank volume. Typically a septic tank must be pumped out at least every 3 to 5 years or more frequently depending on usage.
- Grease traps must be inspected at least quarterly and cleaned out regularly.
- Deep rooting trees or shrubs should not be grown over absorption trenches or pipes.
- Surface water diversion drains should be maintained upslope of and around the land application area and kept clean to reduce seepage of rainwater into the trenches.
- Maintain disposal area by maintaining plants and mowing grass to ensure that plants/grasses take up nutrients with maximum efficiency.
- Check disposal area for blockages such as wet spots and uneven grass colour.

I certify the matters described in this certificate.

Certifier:

	Signed:
burn	~

29/01/2024

Date:



Certificate No.

GL21145Bc